

# UT522 QA测试报告

使用仪器: 电阻箱/FLUKE5520A

环境温湿度: 24.3°C/56%

功能	量程	输出值	准确度	最大允许误差	测试值	测试结果
接地电压	400Vac	1Vac	±(1%±6)	0.4~1.6Vac	1.1Vac	合格
		10Vac		9.3~10.7Vac	10.2Vac	合格
		50Vac		48.9~51.1Vac	49.8Vac	合格
		100Vac		98.4~101.6Vac	100.4Vac	合格
		200Vac		197.4~202.6Vac	199.8Vac	合格
		390Vac		385.5~394.5Vac	389.9Vac	合格
接地电阻	40Ω	1Ω	±2% rdg ±0.2Ω	0.78~1.22Ω	1.02Ω	合格
		10Ω		9.60~10.40Ω	9.98Ω	合格
		20Ω		19.40~20.60Ω	20.02Ω	合格
		39Ω		38.02~39.98Ω	39.03Ω	合格
	400Ω	20Ω	±2% rdg ±3dgt	19.3~20.7Ω	20.1Ω	合格
		100Ω		97.7~102.3Ω	100.2Ω	合格
		200Ω		195.7~204.3Ω	200.1Ω	合格
		390Ω		381.9~398.1Ω	389.8Ω	合格
	4KΩ	200Ω	193~207Ω	201Ω	合格	
		1KΩ	977~1023Ω	1000Ω	合格	
		2KΩ	1957~2043Ω	1998Ω	合格	
		3.9KΩ	3819~3981Ω	3902Ω	合格	

检测员: 张琼

